A Critical Analysis of Nuclear Waste Disposal in Space: An Assessment of Technical, Economic, and Legal Viability

Abstract

Since the start of the nuclear age in the mid-20th century, humanity has struggled with the persistent, multigenerational challenge of high-level nuclear waste (HLW) [8]. This material, primarily spent nuclear fuel from civilian power generation and radioactive byproducts from military defense programs, is extremely toxic and has an extraordinarily long half-life, remaining a significant environmental and public health hazard for hundreds of thousands of years [8]. Although the recycling of most nuclear waste is possible, 3-4% of the total nuclear waste is not recyclable [14]. The internationally accepted long-term management strategy is deep geographic isolation in geologically stable areas. Unfortunately, multiple projects like the United States' Yucca Mountain repository and Germany's proposed Gorleben site have failed due to intense public opposition, political stalling, and scientific debate over geological suitability and environmental cost [7]. Under projected high-growth scenarios for nuclear energy, cumulative HLW could triple by 2070, exceeding the capacity of all planned geological repositories, which creates renewed pressure to evaluate other alternatives. These particular issues have periodically driven scientists and policy analysts to revisit an alternative method, the permanent removal of this waste from the Earth's biosphere by launching it into outer space [3].

This is not a new concept; during the 1970s and 1980s, agencies including the National Aeronautics and Space Administration (NASA) and the former Atomic Energy Commission (AEC) undertook systematic studies to evaluate the technical and economic feasibility of space-based disposal [2]. These foundational analyses concluded that, from a pure engineering and physics standpoint, these concepts were theoretically sound [2]. The principles of orbital mechanics and the required propulsion technology were deemed surmountable challenges. However, the same studies consistently identified two critical challenges: 1) the unacceptably high risk of a catastrophic launch failure, which would disperse radioactive material into Earth's atmosphere, and 2) the restrictions posed by the emerging body of international space law, particularly the 1967 Outer Space Treaty, which limited the use of nuclear materials in space and its environment.

Most comprehensive studies on this topic were completed before 2010, before the recent revolutions in commercial spaceflight led by companies like SpaceX. This paper provides a critical re-evaluation of space disposal, contrasting with the conclusion of historical studies, in light of the dramatic alteration of the technological and economic landscape of the 2020s. It specifically examines the impact of modern reusable launch systems, such as SpaceX's Falcon 9 and Falcon Heavy, which have reduced the cost of access to low Earth orbit by an order of magnitude [4]. While this advancement addresses the historical economic barrier, this analysis argues that the core safety and legal impediments remain not only unresolved, but are in fact increased by the sheer amount of waste inventory. The paper details the two principal disposition endpoints, interstellar ejection and a direct solar impact, and provides cost, risk, and

legal analysis. It concludes that, including current technological progress, space disposal becomes economically possible. One last issue of safety remains. Although statistically low, any launch failure could disperse large amounts of radioactive material across thousands of square kilometers [4]. Therefore, it should be considered a possibility in 20-50 years as a solution to the nuclear waste dilemma, once safety concerns are resolved and the expected radiological release from launch failures is projected to be lower than the expected release from geological repositories over the same timeframe.

Introduction

The management of high-level nuclear waste represents one of the most persistent sociopolitical challenges of the modern era. Globally, the inventory of spent nuclear fuel and other high-level waste has reached approximately 450,000 metric tons, with tens of thousands of additional tons generated annually [8]. This material must be isolated from the biosphere for time scales that are beyond recorded human history. Currently, the scientific and engineering consensus points to deep geological repositories (DGRs) as the only viable long-term solution. These facilities are designed to bury waste hundreds of meters underground within stable geologic formations, employing a multi-barrier system of engineered and natural containment.

However, Efforts to implement DGRs have repeatedly failed, illustrating that the problem is as much political and social as it is technical. In the case of the Yucca Mountain repository in Nevada, USA, following the Nuclear Waste Policy Act of 1982, Yucca Mountain was selected after a nationwide search and years of research. By 2008, the Department of Energy submitted a license application to the Nuclear Regulatory Commission (NRC) after investing an estimated $15 billion [7]. Yet, in 2010, the Obama Administration, citing a lack of agreement from the State of Nevada and other concerns, moved to terminate the project. As summarized in a report by the House Committee on Energy and Commerce, the Secretary of Energy declared that “a geological repository at Yucca Mountain is not a workable option,” and the DOE sought to withdraw its license application [7]. This action left the United States without a permanent disposal pathway, forcing the continued indefinite storage of over 80,000 metric tons of commercial spent fuel at dozens of reactor sites across the country, a situation deemed “unacceptable” by the Blue Ribbon Commission on America’s Nuclear Future [7].

This pattern of failure is not unique to the United States. In Germany, the proposed Gorleben salt dome repository was abandoned in 2020 after 40 years of exploration, public protests, and scientific controversy over the site’s long-term stability. Even in nations making tangible progress, the process is glacial and contested. Finland’s Onkalo repository, the world’s first operational DGR, required over 40 years from initial conception to operational license [11], while France’s Cigeo project continues to face legal challenges and public opposition despite political support [1]. This, combined with genuine geological uncertainties and the ethical challenge of creating a hazard that must be managed for millions of years, has created a crisis of confidence in terrestrial solutions.

It is within this context of terrestrial gridlock that the concept of space disposal periodically resurfaces. The proposition is intellectually sound: if the waste cannot be safely contained on Earth for geological timescales, perhaps it can be permanently removed from the planet altogether. The universe, particularly the Sun, offers a natural gravitational sink and fusion furnace, often seemingly a perfect disposal endpoint. The dramatic reduction in launch costs driven by the reusable rocket revolution, pioneered by SpaceX with its Falcon 9 and Falcon Heavy vehicles, has transformed this idea from prohibitively expensive and conceptual into a solution for proper disposal. The Falcon Heavy, for instance, can deliver

approximately 63.8 metric tons to LEO at a reported cost of around $90-150 million per launch when reusable, making the marginal cost of orbital access cheaper than at any point in history.

This paper critically examines whether this renewal of technical plausibility translates into genuine feasibility. It explores the two primary disposal trajectories identified in historical studies as the only true long-term solutions:

1. Interstellar Ejection: Utilizing gravitational slingshot maneuvers, typically around Jupiter, to propel a payload containing nuclear waste on a trajectory that will escape the Sun's gravitational influence entirely, ejecting it from the solar system.
2. Heliocentric Injection: Executing a propulsive maneuver to cancel Earth's orbital velocity, placing the payload on a direct collision course with the Sun, resulting in its total vaporization and atomization within the solar plasma.

However, moving from concept to reality introduces a suite of profound challenges that extend far beyond orbital mechanics. The shift necessitates a rigorous analysis of the legal and regulatory framework governing activities in outer space, primarily the 1967 Treaty on Principles Governing the Activities of States in the Exploration and Use of Outer Space, including the Moon and Other Celestial Bodies. Key articles of this treaty raise immediate and significant legal barriers, including those containing responsibility (Article VI), absolute liability for damage (Article VII), and the imperative to avoid harmful contamination of space (Article IX).

This paper will argue that while modern rocketry technology has altered the economic variable for feasibility, it has not solved the fundamental problems of safety and international legal permeability. The analysis will show that the combination of the probability of launch failures and preclusive legal restrictions renders space-based disposal of nuclear waste an unviable solution at present, and instead, only a solution when there is an extremely low probability of launch failures.

Historical and Legal Framework

During the 1970s and 1980s, NASA, in collaboration with the Department of Energy, conducted comprehensive feasibility studies on space disposal. These studies, most notably the 1978 "Space Disposal of Nuclear Waste" report, concluded that the concept was technically possible [2]. They proposed using the Space Shuttle to transport waste canisters to orbit, where a reusable "Space Tug" would deliver them to final disposal trajectories, either solar orbit or direct solar impact [2]. The studies estimated the cost would add less than 5% to consumer electricity bills, making it economically plausible [3]. However, they also identified the unacceptably high risk of launch failure as the primary stopper. The Space Shuttle, with a projected 99% reliability, was deemed insufficient. A failure rate better than 99.9% and higher would only be considered for such a hazardous cargo. Modern risk analysis suggests that for a campaign of 10,000 launches, an acceptable failure rate would be approximately 99.99%; these are requirements beyond the magnitude of current commercial rockets. The Challenger disaster in 1986, with a 1.5% failure rate in 135 missions, validated this concern and effectively ended any continuous pursuit of the concept [4].

Additionally, the legal barrier is absolute on this topic. The 1967 Treaty on Principles Governing the Activities of States in the Exploration and Use of Outer Space (the Outer Space Treaty) establishes a comprehensive and international legal framework that directly conflicts with the proposal. Key articles that are relevant to disposal are:

- Article IX: Requiring states to avoid “harmful contamination” of space and to undertake international consultations before proceeding with activities that could cause “potentially harmful interference” with other states’ activities. The deliberate, large-scale introduction of radioactive waste into space is a legal gray area regarding this clause.
- Article VII: Establishes that the launching state is “internationally liable for damage caused by its space object on the surface of Earth or to aircraft in flight.” If a launching state faces absolute and unlimited financial liability for global damages, it is a risk that no single nation would assume.
- Article VI: Further highlights state responsibility for all national space activities, including those conducted by private entities and companies.
- Article II: Prohibits national appropriation of outer space, including the Moon and other celestial bodies. Nations cannot claim exclusive authority over any region in space.
- Article I: The exploration and use of outer space shall be carried out for the benefit and interest of all countries.

In the end, the historical NASA studies left a dual legacy: a technical analysis demonstrating the possibility, with a clear identification of safety and legal issues that prevented its initial adoption in practice. While modern reusable rockets have altered the economic issues, the risk and treaty-based prohibitions mainly limit this idea from becoming a full real-world strategy. Although Article I’s principle of ‘benefit of all countries’ may be argued, it is unlikely to override explicit prohibitions on harmful contamination (Article IX) or absolute liability (Article VII). No nation has tested this interpretation, and this assumption is generally viewed as insufficient justification.

Overcoming these legal barriers would require either a new protocol to the Outer Space Treaty or a binding interpretive agreement among signatory states in the UN. Such an amendment would need to:

1. Explicitly permit solar impact as a form of disposal of non-recyclable HLW
2. Establish a shared liability framework with a capped compensation fund
3. Mandate minimum reliability standards for launching vehicles carrying nuclear payloads

While these tasks look diplomatically challenging, precedents such as the 1972 Liability Convention and the 1979 Moon Agreement demonstrate that space law can evolve to adjust for modern issues.

Projected HLW Growth

Before analyzing space-based disposal, a clear understanding of the situation is essential. The current global HLW inventory stands at approximately 450,000 metric tons, with roughly 12,000 metric tons added annually [8]. In the United States alone, more than 86,000 metric tons of spent nuclear fuel are stored at 85 different storage sites across the country [7]. Additionally, annual HLW production could reach approximately 35,000 metric tons. The United States plans to triple its nuclear energy capacity by 2050 [14]. Following this pattern, cumulative HLW would exceed 1.2 million metric tons by 2070, which is nearly triple today’s inventory.

The capacity of existing and planned geological repositories, however, falls short of this projected volume. Finland’s Onkalo repository, the world’s first operational deep geological repository, will hold approximately 6,500 metric tons of spent fuel [11]. The proposed Yucca Mountain repository in Nevada was limited to 70,000 metric tons, and even under the most optimistic technical capacity, the Yucca Mountain repository remains non-viable [7].

Planned European repositories offer similarly limited capacity. France’s Cigeo project has a reference inventory of approximately 10,100 cubic meters for HLW, which is about 10,000 to 15,000 metric tons

[1]. Sweden's Forsmark repository, approved for construction in 2022 with its completion expected around 2080, has the capacity for 12,000 tons of spent nuclear fuel. However, it is stated by The Economic Times that it "will not hold fuel from future reactors" [5]. Even if all planned European repositories are completed, the total global deep geological repository capacity does not exceed 250,000 metric tons.
This is less than 25% of the projected HLW growth. Below is a table showing the growing disparity:

Scenario	Cumulative HLW by 2070	Total DGR Capacity	Deficit
Current Growth	850,000 metric tons	250,000 metric tons	600,000 metric tons
High Growth	1,200,000+ metric tons	250,000 metric tons	950,000+ metric tons

Even successful repositories are designed only for existing waste, not expanded nuclear capacity, which creates increasing pressure to reconsider space-based disposal options. If nuclear energy expands as projected, the gap between waste production and disposal capacity will demand alternative solutions, of which space disposal is currently the only permanent option that does not rely on future geological repository construction.

Architecture and Process

Assuming near-perfect launch safety, the primary constraints become mass, energy, and time. The following architecture represents an optimized, future-state system for the disposal of the global HLW inventory (~450,000 metric tons). The following plan involves 3 phases: launch to orbit, dock with the station, and disposal launch, with various disposal methods considered, including launch out of the solar system and launch into the Sun.

Phase 1: Earth to Orbit

Phase 1 establishes the terrestrial-to-orbital logistical chain, which is the most cost-intensive and risky part of the mission. Using current concepts of reusable rocket technology, such as SpaceX's Falcon 9, the Zhuque-3 (VTVL-1), and Hyperbola-2Y, the cost of a launch can be reduced by up to 30%, while also increasing launch frequency, payload, and reliability [4]. Some additional operational architecture is required for optimal execution.

1. A dedicated spaceport should be constructed at an optimal equatorial location, minimizing the energy required to reach departure inclinations for interplanetary trajectories and the energy used to reach LEO.
2. A Standardized Payload, or Primary Waste Canister (PWC), should be created. Each launch carries a single, standard PWC, a self-contained, multi-barrier disposal unit. Each unit contains vitrified or glass-encased high-level nuclear waste, with a multi-layer, self-metal matrix used to contain any waste [3]. A thick, dual-purpose shield is composed of an inner boron-based polymer and an outer tungsten or depleted uranium shell. This

shield is designed for launch, orbital handling, and containment in the unlikely case of launch failure.

3. A Logistics Flow, where PWCs are manufactured, inspected, and certified, and a secure, centralized facility. They are transported via a specialized transport to the launch site, where these PWCs are then integrated into the launch vehicle.

Following launch, the vehicle's upper stage will deliver the PWC to an Assembly Orbit, docking with an Orbital Integration Facility (OIF) in orbit. The automated Orbital Integration Facility is constructed at the Assembly Orbit and used to initiate phase 2.

Phase 2: Orbital Consolidation and Preparation for Launch

The OIF is a robotic space station assembled from multiple modules launched. Its primary functions are to receive PWCs, store them temporarily in a radiation-safe location, and then robotically integrate them into larger payloads for disposal. It should feature heavy-duty robotic arms, grapple fixtures, and passive radiation shields to protect its own systems.

1. An orbital tug, or a reusable spacecraft, using high-efficiency Solar Electric Propulsion (SEP). Electron Propulsion Systems use ion thrusters to power the spacecraft using reusable materials and resources. Unlike traditional chemical rockets, EP systems (like Hall effect thrusters or Ion drives) offer high specific impulse, meaning they use propellant much more efficiently over time [9].




Figure 1: NASA. "4.0 In-Space Propulsion." *State-of-the-Art of Small Spacecraft Technology*, 10 Oct. 2021, www.nasa.gov/smallsat-institute/sst-soa/in-space_propulsion/.

2. The Ionization Process: The core of this system involves ionizing a noble gas, typically Xenon, by stripping away electrons to create a stream of positive ions [9]. By utilizing solar energy collected via high-yield photovoltaic arrays, these ions are accelerated through an electrostatic field.
3. Momentum and Efficiency: Following Newton's Third Law of Motion, these ions are expelled from the thruster at exhaust velocities reaching approximately 90,000 m/s [9].

Unlike chemical rockets that burn fuel quickly for high thrust, Ion Drives provide a much higher specific impulse. This allows the spacecraft to remain in the exosphere for extended periods without the need for frequent, heavy refueling.

Because the energy source is solar and the propellant consumption is minimal, the "Earth-to-Orbit Bridge" becomes a low-cost, repeatable loop for waste transport.

The tug is used to retrieve PWCs from their initial drop-off point in the Assembly Orbit and deliver them to the OIF. The OIF includes many attachments, including a robotic arm.

Phase 3: Orbital Cargo Integration:

Once the autonomous electric shuttle arrives, the mission shifts from transport to payload processing. This phase is designed to ensure maximum safety before the final "no-return" trajectory toward the Sun is initiated.

1. Automated docking procedure: The system uses an autonomous Guidance, Navigation, and Control (GNC) system to dock. Details on the autonomous GNC system are provided below [10]:

This architecture ensures the safe transit of hazardous materials through the exosphere to the docking port.

a. Guidance: Path Planning: The guidance system calculates the optimal trajectory from the launch injection point.

b. Fuel Optimization: It uses "Lambert's Problem" algorithms to determine the most fuel-efficient transfer orbits, ensuring the Ion Drive's low-thrust profile is utilized effectively [10].

c. Collision Avoidance: The system cross-references real-time data from the Space Surveillance Network (SSN) to automatically adjust its path and avoid orbital debris [4].

d. Navigation: State Estimation: The navigation subsystem determines the spacecraft's current position and velocity (its "state") [10].

e. Sensors: It employs a suite of Star Trackers, Inertial Measurement Units (IMUs), and Global Navigation Satellite System (GNSS) receivers [10].

f. Relative Navigation: As the craft nears the OIF, it switches to LiDAR (Light Detection and Ranging) and optical cameras to measure the exact distance and orientation (pose) relative to the station's docking adapter.

g. Control: Precise Maneuvering: The control system executes the commands from the guidance system by translating them into thruster firings.

h. Reaction Control System (RCS): While the Ion Drive provides the primary forward thrust, a secondary set of cold-gas or electric micro-thrusters manages the "attitude" (the direction the craft is pointing).

i. Six Degrees of Freedom (6DoF): The GNC system manages movement across all axes, allowing for the "soft-docking" required to safely transfer nuclear cargo without damaging the OIF structure.

2. Robot hand-off: Robotic hand-off for less risk. The station's robotic arm (like the Canadarm2) extracts the shielded nuclear canisters from the shuttle's cargo bay.




Figure 2: NASA. "Mobile Servicing System." *NASA.gov*, 20 June 2023, www.nasa.gov/international-space-station/mobile-servicing-system/.

   a. Radiation Containment: The cargo remains in Universal Transport Casks (UTCs), multi-layered containers made of lead, boron-carbide (for neutron absorption), and a titanium outer shell to prevent any leakage onto the station.

3. Assembly Solar Insertion Capsules (SICs): The OIF serves as the point of assembly for the Solar Insertion Capsules (SICs). While the shuttles are built for reuse, the SICs are "single-use" kinetic projectiles designed for one-way travel.
   a. Ballistic Securing: Specialized station robots secure the waste canisters in the SICs.
   b. Ablative Shielding: Each SIC is equipped with a thick carbon-carbon heat shield. This isn't for atmospheric reentry, but for the intense thermal flux. It represents heat flow in a specific direction (a vector quantity), commonly driven by temperature differences from hot to cold. Types include conduction, convection, and radiation, essential for optimizing thermal insulation, electronics cooling, and energy efficiency. To do this, we can use the heat flux equation, which provides a comprehensive, vector-based picture of how heat moves—both its magnitude and direction—rather than just a single temperature reading [12].

4. Safety Verification: The OIF is an area where robots can perform final checks toward safety.
    a. Leak Detection: Sensors on the OIF scan the canisters for gamma-ray spikes or structural micro-fractures caused by the launch.
    b. Trajectory Calibration: The OIF mission control calculates the precise "departure window." Because the Sun is a moving target and Earth is orbiting at high speeds, the SIC must be released at the exact millisecond to ensure it doesn't accidentally enter a stable orbit or fly toward another planet.
5. At the OIF, multiple PWCs are connected to form a rigid stack. This stack is then used in the third and final phase.

Phase 3: Final Disposal

Phase 3 is a terminal launch to remove HLW permanently. The phase, however, confronts a core physics problem: achieving the large amount of velocity change (Delta-V) required for permanent disposal. Two primary destinations are considered, each with different energy requirements when launched from the Assembly Orbit:

- Option A: Solar System Escape via Jupiter Gravity Assist. This is the more energetically efficient solution. The DPS provides a ΔV of ~8-10 km/s to send the PWC stack towards Jupiter. A flyby uses the planet's gravity to slingshot the payload to solar escape velocity, ejecting it from the solar system forever. Although there is a multi-year transit time to Jupiter, this minimizes the propellant needed from Earth.
- Option B: Direct Solar Impact. This is more conceptually simple, but energetically more expensive. It requires the DPS to provide a Δv of ~24-30 km/s to cancel Earth's orbital velocity and send the payload into the Sun. The waste would be vaporized within the solar corona, but the propellant mass required for this option is exponentially greater than for JGA.

Propulsion Methods

Both methods will use several propulsion stages. The Disposal Propulsion Stage (DPS): The DPS can be single-use or reusable. It is a stage dedicated to the final disposal burn. It determines the entire project's feasibility. Chemical rockets are impractical due to their low efficiency. The only plausible technology for this scale is:

1. Nuclear Thermal Propulsion (NTP): Using a compact fission reactor to heat liquid hydrogen propellant, offering roughly double the efficiency of chemical rockets [6]. It provides the high thrust needed for this project.
2. Nuclear Electric Propulsion (NEP): Using a fission reactor to generate electricity, which powers advanced ion or plasma thrusters [9]. It offers an extremely high efficiency, but a very low thrust, resulting in trajectories that take decades to depart Earth's surrounding area.

In this context, we will assume the development of a high-thrust NTP-based DPS. After integrating with the PWC stack at the OIF, the DPS ignites for a single, prolonged burn, injecting its payload onto the chosen trajectory. The DPS will then be separated to be reused in future launches.

A theoretical third launch option could involve utilizing non-rocket technology to circumvent the traditional risks and costs of the first stage ascent. The most developed concept in this category is the SpinLaunch kinetic launch system [13].

Instead of using a reusable rocket, a ground-based, vacuum-sealed centrifuge spins the payload at hypersonic speeds. The payload, housed within a specialized launch vehicle, is then released through a launch tube directed skyward. The initial kinetic boost, which provides a significant portion of the velocity needed to reach orbit, is followed by a small, conventional rocket motor attached to the launch vehicle that takes over to circularize the orbit [13].

In nuclear waste disposal, the PWC would be enclosed in a SpinLaunch Mass Accelerator (SLMA) pod. This pod is engineered to withstand the immense rotational and linear g-forces during the spin-up and release. The state itself would likely need to be processed into an ultra-stable state to prevent any microfracturing under extreme stresses. The shielding would also need to be homogeneously distributed and bonded to the core to maintain structural integrity.

Advantages of this Model:

1. Elimination of First-Stage Propellant Risk: By removing the large quantities of explosive chemical propellants from the initial launch phase, the risk of a catastrophic explosion is negated [13].
2. Potential for Ultra-High Cadence and Lower Cost: The system is electrically powered and designed for multiple launches per day. The marginal cost per launch, after the massive expenses of building the facility, could be orders of magnitude lower than any chemical rocket, potentially driving costs towards $1000/kg for the initial launch [13].
3. Environmental Impact: The system would be carbon-neutral during the launch phase, using grid electricity.

Challenges and Limitations:

1. Scale and Payload Mass: Current SpinLaunch technology is suborbital and designed for a ~200 kg satellite-class payload. Scaling this to launch a 150 metric ton PWC represents an engineering challenge, requiring a centrifuge of unimaginable scale and material science beyond current technological limits.
2. G-Forces: While electronics can be hardened, ensuring a multi-ton complex shielded canister containing brittle vitrified waste survives 10,000+ Gs without compromising its containment barriers is an unproven and potentially limiting hurdle. Any flaw could turn the launch into an international nuclear incident.
3. Atmospheric Transit: The hypersonic transit through the dense lower atmosphere would generate extreme thermal and aerodynamic stresses, resulting in the high-velocity impact and disintegration of the PWC, posing a severe contamination risk.
4. Incomplete Solution: Even if the launch is successful, SpinLaunch only solves the first ~ 2km/s of the required ~9.4 km/s to reach LEO. A large, reliable upper-stage rocket is still required, which does not mitigate propulsion risks and comes at a high cost [13].

Ultimately, while SpinLaunch is a theoretical alternative that directly addresses the propellant-explosion risk of traditional rockets, its application to nuclear waste is more speculative than advanced reusable

rockets. This model does not follow the idealized safety standards required for a project of such a degree. Thus, this launch type may be incompatible with the fragility of its intended payload.

Analysis

While the current theoretical framework for space disposal of nuclear waste exists, current technology falls short of making it a viable solution.

1. Launch Reliability and Scale

Current launch systems are only at a 98-99% success rate and are inadequate for transporting nuclear waste [4]. For a project requiring thousands of launches, even a 1% failure rate guarantees multiple incidents. The industry has not yet developed the necessary Failure Modes and Effects Analysis (FMEA) or backup mechanism that would be required for hazardous material transport. Rocketry remains a complex problem where systems operate at the edge of material science limits. Perfect reliability is an engineering impossibility with current technology.

2. Radiation Shielding Problem

Current space-rated radiation shielding technology is massive. The multi-layer tungsten/boron carbide shielding required for high-level waste transportation adds 50-100% mass overhead to the payload. This creates an additional economic problem. For every kilogram of waste disposed of, 1.5-2 kilograms must be launched. With the current launch costs of approximately $2000/kg, the economics remain questionable [3].

3. In-Space Propulsion Gap

The critical technology for economic disposal does not yet exist. Chemical rockets lack the efficiency, while current electric propulsion lacks the necessary thrust. Nuclear Thermal Propulsion (NTP) is the most promising technology for this application, but it remains in the demonstration phase. NASA's DRACO program aims for a 2027 test, but operational, human-rated systems capable of regular heavy-lift disposal missions are 20-30 years from maturity [6]. Infrastructural and Logistical Hurdles also exist.

4. No Specialized Launch Infrastructure

Current spaceports are designed for satellites and crew, not for thousands of multi-ton radioactive payloads. The required facilities, such as processing buildings, remote integration facilities, specialized transport systems, and emergency response infrastructure for nuclear materials, would need to be designed and built from scratch. The regulatory approval process alone for such facilities would take years.

5. Orbital Infrastructure Gap

The proposed Orbital Integration Facility (OIF) does not currently exist. The International Space Station, while demonstrating a long-term orbital presence, is unsuitable for handling nuclear waste due to crew radiation risks, and it is reaching the end of its service lifespan. Building a large, automated,

radiation-hardened orbital facility represents a space construction process orders of magnitude more complex than the ISS, requiring technologies that are still currently being developed.

6. Supply Chain Limitations

The manufacturing capacity for standardized waste canisters at the required scale does not currently exist. The specialized materials, quality control processes, and certification standards for space-rated nuclear containment would need to be developed. Similarly, the launch industry cannot currently support the required launch rate. Global launch capacity is approximately 100-150 launches per year across all providers and countries. A disposal campaign would require sustained rates of 50-100 more launches per year for decades, for waste disposal.

Economic Barriers

1. Prohibitive Current Costs

Even with reusable rockets, current costs in order to reach LEO make the disposal economically difficult. The $1 trillion in launch costs alone makes space disposal economically prohibitive [4]. When compared to terrestrial geological repositories, space disposal is about 10 times more expensive with current technology.
The following cost estimates assume a full disposal campaign for the current global HLW inventory of 450,000 metric tons, using direct solar impact as the disposal impact.

Cost Category	Unit Cost	Quantity	Subtotal
Launch to LEO	$2,000/kg	450,000 metric tons	$900 billion
Radiation Shielding	$2,000/kg	225,000 metric tons	$450 billion
Nuclear Thermal Propulsion Stage	$50 billion	1 program	$50 billion
Orbital Integration Facility	$100 billion	1 facility	$100 billion
Dedicated Equatorial Spaceport	$25 billion	1 facility	$25 billion
Primary Waste Canister Manufacturing	$50,000 per canister	450,000	$22.5 billion
Ground infrastructure and logistics	$10 billion annually	30 years	$300 billion
Regulatory and Legal Framework	$5 billion	1 program	$5 billion

Development			
Contingency	25%	$1,852.2 billion	$463 billion

Total Estimated Cost: $2.315 trillion

Below is a comparison of the cost with a deep geological repository:

Disposal Method	Estimated Total Cost	Cost per Metric Ton
Deep Geological Repository	$225 billion	$500,000
Space Disposal	$2.315 trillion	$5.1 million

Key Drivers of Cost:

1. Shielding mass overhead
2. Orbital infrastructure
3. Campaign duration

However, if launch costs fall to $500/kg(SpaceX Starship's target), total costs drop to approximately $800 billion, which approaches the cost with multiple geological repositories [4].

(Note: All cost estimates are projections based on current launch prices and historical space infrastructure costs. Actual cost would vary significantly based on technology maturation and international cooperation.)

Insurance and Liability Markets

The insurance industry has no products for, and no data on, insuring thousands of nuclear waste launches. The liability for a single failure, which could cause global contamination, is essentially uninsurable. The 1972 Liability Convention's provisions for absolute state liability mean that any nation undertaking this would be assuming potentially unlimited financial risk.

Legal and Regulatory Barriers

1. Treaty Prohibitions

The Outer Space Treaty explicitly prohibits "harmful contamination" of space, and any large-scale waste disposal could be challenged as a violation. Additionally, our global opposition could arise.

2. No Regulatory Framework

No space agency or international body has developed regulations for the launch, orbital handling, or disposal of nuclear waste in space. The entire framework, from payload safety standards to orbital traffic management for hazardous materials, would need to be created. The Nuclear Regulatory Commission (NRC), Federal Aviation Administration (FAA), and international equivalents have no protocols for this scenario.

Sociopolitical Realities

1. Public Acceptance

Public opposition to nuclear waste transportation on Earth is already significant. The concept of launching it overhead thousands of times would face immense public resistance [4].

2. International Opposition

Given that launch failures could contaminate the atmosphere, the proposal would face some international opposition. Countries without space programs or those downrange of launch trajectories would have strong incentives to block the programs [4].

Summary

Space-based nuclear waste disposal remains a theoretical solution because it requires technologies, infrastructure, legal frameworks, and economic conditions that do not currently exist. The gaps are not small improvements, but breakthroughs across multiple areas. The solution requires advancements in rocket reliability, propulsion efficiency, and space infrastructure, requiring a convergence that will likely occur within 20 to 50 years.

The most rational steps for the coming decades are to continue the development of the technologies necessary for space disposal, while addressing the nuclear waste problem on Earth through continued recycling and geological storage. And once space technologies mature sufficiently, the option for space disposal will be viable for the unrecyclable HLW, marking it as a potential solution for future advanced reactors.

Path Forward

Given the technical, economic, and legal gaps identified in this paper, space-based nuclear waste disposal cannot be implemented today. However, a phased approach over 20-50 years could address these barriers incrementally.

Phase 1: Research and Demonstration

0-10 years

Objective	Specific Actions
Launch Reliability	Fund development of ultra-reliable launch systems targeting 99.99% reliability. Mandate FMEA for nuclear payload launches [4].
Nuclear Thermal Propulsion	Support NASA's DRACO program and international counterparts. Achieve a demonstration by 2030 [6].
Radiation Shielding	Research advanced materials to reduce mass

	overhead from 50% to less than 20%.
Legal Groundwork	Initiate discussions among IAEA member states on a potential amendment to the Outer Space Treaty protocol for solar disposal.

Estimated cost: $10-15 billion over 10 years.

Phase 2: Infrastructure Development

10-25 years

Objective	Specific Actions
Dedicated Launch Infrastructure	Construct an equatorial spaceport with nuclear-certified handling facilities.
Orbital Integration Facility	Deploy a robotic, radiation-tested orbital station.
Standardized Waste Canisters	Develop and certify the Primary Waste Canister (PWC) design with multi-layer shielding [3].
Legal Framework	Negotiate and ratify a new treaty protocol establishing liability caps, safety standards, and inspection regimes.

Estimated cost: $150-200 billion over 15 years

Phase 3: Pilot Disposal Campaign

25-50 years

Objective	Specific Actions
Pilot Launch	Conduct a single demonstration launch by sending a small quantity of HLW to solar impact.
Performance Validation	Verify launch reliability and orbital handling trajectory accuracy.
Liability Testing	Establish an international insurance and compensation framework.
Full Campaign	If testing passes, initiate full-scale disposal at a rate of 50-100 launches per year.

Estimated cost: $10-50 billion for testing, 2+ trillion for full campaign

Parallel Track

While space technologies are developing, the following should proceed in parallel:

- Complete and operate Finland's Onkalo repository as a proof-of-concept [11]
- Restart licensing for Yucca Mountain or identify a new U.S. geological repository [7]
- Expand recycling and reprocessing to reduce the fraction requiring permanent disposal [14]
- Fund research into advanced reactors that produce less long-lived waste [14]

Decision Gate

Before proceeding from Phase 2 to Phase 3, the international community should establish a formal decision gate, requiring:

1. Demonstrated launch reliability of greater than 99.99% over 1,000 consecutive launches [4]
2. Ratification of the treaty protocol permitting space disposal
3. Establishment of a multinational liability fund
4. Successful completion of an uncrewed test mission with no anomalies

(Note: This pathway assumes sustained political will and international cooperation, which cannot be guaranteed)

With these steps, Space Disposal for nuclear waste could be a major viable option within 20-50 years.

References

[1] Andra. "The Proposed Operations Master Plan of Cigéo - 17013." *WM2017 Conference*, 5-9 Mar. 2017, Phoenix. *OSTI*, www.osti.gov/biblio/22794449.

[2] Burns, R. E., et al. *Nuclear Waste Disposal in Space*. NASA Technical Paper 1225, National Aeronautics and Space Administration, May 1978. *NASA Technical Reports Server*, ntrs.nasa.gov/api/citations/19780015628/downloads/19780015628.pdf.

[3] Coopersmith, Jonathan. "Disposal of High-Level Nuclear Waste in Space." *Space Manufacturing Conference*, 1999, pp. 111-115. *National Space Society*, nss.org/wp-content/uploads/Space-Manufacturing-conference-12-111-Disposal-Of-High-Level-Nuclear-Waste-In-Space.pdf.

[4] Department of Energy. "3 Reasons Why We Don't Launch Nuclear Waste into Space." *Energy.gov*, 5 Apr. 2023, www.energy.gov/ne/articles/3-reasons-why-we-dont-launch-nuclear-waste-space.

[5] *The Economic Times*. "Sweden Starts Building 100,000-Year Storage Site for Spent Nuclear Fuel." Jan. 2025.

[6] Foust, Jeff. "Making a New Case for Space Nuclear Power." *The Space Review*, 21 July 2025, www.thespacereview.com/archive/5028-1.html.

[7] House Committee on Energy and Commerce. *Yucca Mountain*. Republicans on the House Energy and Commerce Committee, republicans-energycommerce.house.gov/yucca-mountain. Accessed 29 May 2026.

[8] International Atomic Energy Agency. *Status and Trends in Spent Fuel and Radioactive Waste Management*. IAEA, 2022.

[9] NASA. "The Propulsion We're Supplying, It's Electrifying." *NASA.gov*, 22 Oct. 2020, www.nasa.gov/humans-in-space/the-propulsion-were-supplying-its-electrifying/.

[10] NASA Science. "Chapter 2: Reference Systems." *Basics of Space Flight*, science.nasa.gov/learn/basics-of-space-flight/chapter2-1/. Accessed 29 May 2026.

[11] Posiva. "Introducing ONKALO and Its Principle of Operation." *Posiva.fi*, 3 July 2024, www.posiva.fi/en/index/news/pressreleasesstockexchangereleases/2024/thisisonkaloandthisishowitworks.html.

[12] SimScale. "What Is Heat Flux?" *SimScale Documentation*, 20 Nov. 2023, www.simscale.com/docs/simwiki/heat-transfer-thermal-analysis/what-is-heat-flux/.

[13] SpinLaunch. *SpinLaunch*, www.spinlaunch.com. Accessed 29 May 2026.

[14] Tuhus-Dubrow, Rebecca. "Recycling Nuclear Waste: A Win-Win or a Dangerous Gamble?" *Yale Environment 360*, Yale School of the Environment, 2 Apr. 2025, e360.yale.edu/features/nuclear-waste-recycling.